


STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION









PROPOSED INTERIOR PARAPET SECTION


Notes:


- 1. Existing reinforcement bars extending into the concrete removal area shall be blast-cleaned, straightened and incorporated into the new construction. Any reinforcement bars that are damaged during concrete removal shall be repaired or replaced with an approved bar splicer or anchorage system. Cost included
- 2. Existing reinforcement bars in the concrete removal area parallel to the expansion joints shall be removed.
- 3. Removal and disposal of the existing expansion joints will not be paid for separately, but shall be included with the cost of Concrete Removal.
- 4. If existing name plate falls within the limits of Concrete Removal, It shall be removed and reinstalled in its original location in accordance with IDOT Std. 515001. Cost included with Concrete Superstructure.
- 5. If existing guardrail and/or end shoe fall within the limits of Concrete Removal, they shall be removed and reinstalled in their original location in accordance with District 1 Std. BM-21. Cost included with Concrete Superstructure.
- 6. Work this sheet with Expansion Joint Repairs sheet.

SECTION A-A









PROPOSED EXTERIOR PARAPET SECTION

EXPANSION JOINT DETAILS STRUCTURE NO. 022-0096

alfred benesch & company benesch Surveyors - Planners 205 North Michigan Avenue, Suite 2400 Chicago, Illinois 60601 312-565-0450 Job No. 10050

HEET NO. 6	F.A.I. RTE.	SECTION		
	290	22(1,	1-1,	2&3)R
9 SHEETS				
	FED DOAD	DICT NO	`	TI I TNIO

COUNTY 546 DUPAGE 3:14 CONTRACT NO. 60G51 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT